

IBUILT'S LVL SCAFFOLD PLANK

April 2023

IBuilt Plank Specification

STATUS PLANK

| Section Size: | 42mm x 230mm |
|---------------|---------------------|
| Length: | 3.0m, 3.6m and 4.2m |
| Unit Weight: | 5.4kg/m |

lumber (LVL) product supplied from Nelson Pine Industries. IBuilt Plank is an essential part of any construction project where safe off-ground work is required. Strong, durable and reliable, they are made to walk on, carry a load, and can stand up to the elements.

IBuilt Scaffold Planks are a structural laminated veneer

IBuilt Plank is independently certified by the Engineered Wood Products Association of Australasia and made in accordance with strict and quality environmental standards.

All IBuilt Planks are manufactured from FSC certified Radiata Pine.

IBuilt Plank. Straight, true and strong.

Surface finish: Unsanded faces, arrised edges and square cut, painted sealed ends. Embossed Branding:

| NP Plank | Proof tested Scaffold Plank | Made in New Zealand | AS/NZS 4357.0 EWPAA MILL 919 | | | |
|----------|--------------------------------|------------------------|--------------------------------------|-------------------|--------------------|--------------------------------|
| NP Plank | Proof tested Scaffold Plank | Test Date | AS/NZS 1577 - 2013 EWPAA MILL 919 | Light 2.4m Max | Medium 2.0m Max | Heavy 250KG UDL 1.8m Max |

Quality Control and Structural Verification

IBuilt Plank is manufactured and tested in accordance with the quality controlled process in AS/NZS 4357. Compliance with this process is third party audited by the Engineered Wood Products Association of Australasia (EWPAA). The EWPAA is a Joint Accreditation System of Australia and New Zealand (JAS-ANZ) accredited Product Certification body. Each IBuilt Plank is individually proof tested to verify the strength of each IBuilt Plank exceeds the bending moment requirements for the working loads set out in the Live Load Duty Category Table 1 below.

Table 1. Scaffold Platform Duty Categories (as per AS/NZS 1576 & 1577) for IBuilt Plank

| Live Load Duty Category | Maximum Span (m) | Working Load Limit (WLL) |
|-------------------------|------------------|-------------------------------------|
| Light Duty | 2.4 | 2.2kN (inc 1.2kN concentrated load) |
| Medium Duty | 2.0 | 4.4kN (inc 1.5kN concentrated load) |
| Heavy Duty | 1.8 | 6.6kN (inc 2.0kN concentrated load) |

1kN is approximately 100kg.

Applicable Design Standards

- AS/NZS 4357:2005 Structural Laminated Veneer Lumber
- AS/NZS 1576:2010 Scaffolding General Requirements
- AS/NZS 1577:2013 Scaffold
 Decking Components
- AS1720:2010 Timber Structures

2 9 0-8 1 4 ASINZS 1577-2013 LIGHT MEDIUM HEAVY 250KG UDL NP PLANK

Care, Maintenance and Storage

Avoid Damaging IBuilt Plank

- Do not use IBuilt Plank over greater spans than those recommended for each Duty
- · Category.
- · Do not drop or throw IBuilt Plank from excessive heights.
- · Do not drop heavy materials or jump on IBuilt Plank.
- Do not drive over IBuilt Plank.
- Notching, cutting or machining IBuilt Plank will reduce its strength.
- Take precautions against slag burns from gas cutting or welding.

Chemical Effects

Radiata Pine veneers are largely unaffected by exposure to moderate strength acids or alkalis (in the pH range 3-9). Strong concentrations of acids or alkalis will affect the lignin which binds wood fibre. The phenolic resin used to bond IBuilt Plank is highly resistant to chemical attack. Planks used in these conditions should be regularly evaluated before reuse.

Decay

Under normal service conditions, planks subjected to wetting and drying cycles are not likely to decay. Typically decay is caused by storing the planks wet and not storing them appropriately to allow them to dry. Planks that show any evidence of fungal decay should be allowed to dry then evaluated for strength before use.

Storage Recommendations (Also refer to AS/NZS1577 section 5.8 Storage During Service Life)

- Dry planks can be stacked on top of one another, well clear of the ground and covered to keep dry.
- Wet planks should be stacked in a dry, well ventilated area clear of the ground, with spacers/fillets aligned between each layer to allow air flow to dry out the planks.
- The stack should be level, neatly stacked and supported with aligned bearers and spacers not greater than 2.0m apart.

Visual Inspection to ensure planks are safe to use (Mechanical testing should also be performed periodically)

Plank performance is compromised when the following conditions are evident:

- End splits through plank thickness (exceeding twice the plank width) could be an indication a plank was dropped.
- Separation of veneer layers could be an indication a plank was speared with a forklift.
- Face splits across the face of a plank could be an indication of plank having been overloaded.
- Discoloration could be an indication of decay or fungal attack.
- Soft wood fiber could indicate chemical contamination or insect damage.
- Dents or gouges on the face of a plank could indicate an impact force that overstressed the plank.
- · Saw kerfs through plank thickness will definitely compromise plank performance.
- · Drilled holes and cut notches will definitely compromise plank performance.
- Inspect planks for damage after each use and be sure to evaluate each side of each plank.
- Establish a method to mark each plank after visual inspection and maintain inspection records.



Plantation Grown. All veneers used in the manufacture of NelsonPine LVL are peeled from sustainable plantation grown Pinus Radiata logs.



149 Kerrs Rd, Wiri, Auckland

PO Box 76412, Manukau, Auckland 2241, New Zealand

Tech Info Line: 0800-022-352

Phone: +64-9-268 6540

sales@ibuilt.co.nz techinfo@ibuilt.co.nz

www.ibuilt.co.nz